

**DOCUMENT 00 11 00**  
**ADVERTISEMENT FOR BIDS**

**CITY OF OTSEGO**  
**WELL #1 AND PUMPHOUSE #1 IMPROVEMENTS**

Sealed Bids for the construction of the Well No. 9 and Pumphouse No. 1 Improvements, Improvement Project No. 20-04 will be received by the City of Otsego, at the office of the City Clerk, 13400 90th Street NE, Otsego, MN 55330, until 2:00 p.m. Tuesday, March 17, 2020, at which time the Bids received will be publicly opened and read aloud.

Principal components of the project include the following:

New Well; drill approximately 300 feet deep into the Mt. Simon aquifer, installing 24" outer casing and 18" inner casing, installing 125 HP – 1200 gpm submersible well pump & motor, installing 10" DIP raw water line from existing stub to new well, installing new enclosure control panel to operate the new well, special sediment control and filtering of drilling and well flushing discharges, restoring of site. Inside Pumphouse #1; installing 8" ductile iron piping, appurtenances inside Pumphouse #1.

**WELL #9 SITE**

REMOVE EXISTING VALVE MANHOLE & WELL APPARATUSES	1	LS
REMOVE BITUMINOUS PAVEMENT	35	SY
ABANDON EX. 6" PIPE INPLACE	1	LS
SITE GRADING	1	LS
CLASS 5 AGGREGATE BASE	136	TON
TYPE SP 12.5 NON WEAR COURSE (2,B)	60	TON
CONCRETE PAD WITH CONDUITS (6" THICK)	48	SF
CONNECT TO EXISTING WATERMAIN	1	LS
10" DUCTILE IRON PIPE CL 52	120	LF
DUCTILE IRON FITTINGS	350	LBS
DRILL & DRIVE 24" WELL CASING	80	LF
DRILL 23" OPEN HOLE	253	LF
F&I 18" CASING	255	LF
F&I AND REMOVE DEVELOPMENT EQUIPMENT	1	LS
WELL DEVELOPMENT	60	HRS
HAUL AWAY SANDSTONE	25	CY
F&I WELL SCREEN & GRAVEL PACK	75	LF
TEST PUMPING	50	HRS
CONTROL PANEL W/VFD AND CONTROLS & INSTRUMENTS	1	LS
PANEL DISCONNECT SW	1	LS
GENERATOR RECEPTICAL	1	LS
ELECTRICAL MOB, CIRCUITRY AND INSTALL MISC	1	LS
INSTALL ANTENNA POLE	1	LS
ELECTRICAL MAIN 300A FEEDER IN CONDUIT	175	LF
TURF ESTABLISHMENT & EROSION CONTROL	1	LS

**PUMPHOUSE #1 SITE**

REMOVE EXISTING 6" PIPE AND APPURTENANCES	1	LS
F&I 8" DUCTILE IRON PIPE AND APPURTENANCES	1	LS
INSTALL 8" BADGER MAG METER (CITY SUPPLIED)	2	EA
PAINT AND/OR REPAINT ALL DUCTILE IRON PIPE	1	LS
TESTING	L	LS

Bids will be received for a single prime Contract. The Contract Documents may be examined at the following locations:

City of Otsego  
13400 90th Street NE  
Otsego, MN 55330

Hakanson Anderson  
3601 Thurston Avenue  
Anoka, MN 55303

Bidding Documents may be obtained from the Issuing Office of: Hakanson Anderson, located at 3601 Thurston Avenue, Anoka, MN 55303 for a non-refundable purchase price of \$75 per set.

Alternatively, digital copies of the Bidding Documents are available at [www.haa-inc.com](http://www.haa-inc.com) under the "Projects/QuestCDN" link for \$20.00 (non-refundable). These documents may be downloaded by selecting this project and by entering eBidDoc™ Number 6860573 on the "Search Projects" page. For assistance and free membership registration, contact QuestCDN at (952) 233-1632 or [info@questcdn.com](mailto:info@questcdn.com).

Each bid must be accompanied by a certified check, cashier's check, cash deposit, or bid bond, made payable to the City of Otsego, in the amount of five percent (5%) of the bid.

The City Council reserves the right to reject any and all bids and to waive irregularities and informalities therein and further reserves the right to award the contract in the best interests of the City.

CITY OF OTSEGO

---

Tami Loff, City Clerk

Date: February 24, 2020

Posted: February 25, 2020 on the City of Otsego website @ <http://www.ci.otsego.mn.us/> >Doing Business>Bids  
February 25, 2020 on the Hakanson Anderson website @ <http://www.haa-inc.com/>  
February 25, 2020 on the QuestCDN website @ <https://www.questcdn.com/>